Addendum Number 9816GE Date March 5, 1998 Page Three

location as per OBBC Section M-309.4.1. Smoke detector trouble conditions shall activate a visible or audible signal in an approved location and shall be identified as air duct detector trouble. The mechanical contractor shall conduct a smoke test on the HVAC units witnessed by the building inspector to verify fan shut-down and signal activation upon smoke detection.

- 14. Interior finish materials shall comply with requirements listed in OBBC Table 803.4 and 805.3.
- 15. Submit modifications to the existing sprinkler system for approval per 903.2..
- 16. Provide the required amount of outdoor ventilation air to the office areas as required per table M-1604.3.

You have the right to adjudicate items in this letter within 30 days of the mailing of this notice to the State of Ohio Board of Building Appeals by filing the attached form with the Building Official, Joseph Busch pursuant to 4101:2-1-35 OAC and 4107.05 Columbus Code. You may be represented by counsel, present arguments, oral or in writing, present evidence and examine witnesses appearing for or against you.

| SIGN   | ATURE 29 BULLIM              | DATE 3-20-98    | _ |
|--|------------------------------|-----------------|---|
|  | OWNER OR AUTHORIZI           | ED AGENT        |   |
| PRINT  | NAME                         |                 | _ |
| * The owner or his representative will sign all copies of this addendum. The building permit is not valid unless this signed addendum is attached to the drawings. |                              |                 |   |
|  | FIELD INSPECTION OF DRAWINGS | BY:             |   |
|  | STRUCTURE                    | HEATING         |   |
|  | PLUMBING                     | REFRIGERATION   |   |
|  | ELECTRIC                     | FIRE PROTECTION |   |